



**Each 6 Ft. Section
Consists of:**
2 GaugePad
4 Field Pads
4 Stabilizer Rods

Notes: Ties are to be spaced 18" on center through the crossing. No rail joints through the crossing, rail must be welded.

HiRAIL

HiRAIL Corporation

Full Depth Rubber
Concrete Ties with Stabilizer Rods

Drwg: System Conc Ties Rod	Drawn: wjb 012805	Rev.
	Rev. wjb 073013	Rev.
	Rev.	Rev.